

Ref. No: JBC/Cons/NIQ/2024/2

Date: 23.07.2024

Short Notice Inviting Quotation

Sealed quotations with validity of at least 60 days are invited from APWD registered bidders (all classes) having valid APWD registration certificate, labour license, PAN, and GST return certificate for the work detailed below. Details of the work can be obtained from the Office of the Technical Supervisor, J. B. College till 11:00 AM on 27-07-2024.

| Name of work: painting and false ceiling work for the establishment of the Office of the Vice Chancellor | | | |
|---|--|-------------|------------|
| S. No. | ITEM | UNIT | QTY |
| 1 | Providing and applying white cement-based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. | sqm | 447.00 |
| 2 | Finishing walls with water proofing cement paint of required shade (Two or more coats applied @ 3.84 kg/10 sqm). | sqm | 447.00 |
| 3 | Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade (Two or more coats applied @ 1.43 ltr/ 10 sqm. over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) | sqm | 447.00 |
| 4 | Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks) | sqm | 109.00 |

Terms and conditions:

1. Tender papers may be submitted in the drop box kept in front of the Office of the Principal up to 1:00 pm of 27-07-2024, and opened on the same day at 3:00 pm in the office of the undersigned.
2. Authority reserves the right not to award the contract in unavoidable circumstances.
3. For all clarifications regarding site conditions, items of works or any other related queries, the tenderers may contact the Technical Supervisor, J. B. College during office hours.


Principal

J. B. College, Jorhat

Copy to:

1. Notice board for display.
2. Website for upload.
3. Office file

Principal
J. B. College, Jorhat